



APPIAN Consulting Engineers

**GENERAL NOTES:**

1. CURB INLET DESIGN SPECIFICATIONS CONFORM TO LATEST ASTM C913 SPECIFICATIONS FOR "PRECAST CONCRETE WATER AND WASTEWATER STRUCTURES", NCDOT AND CITY OF GREENSBORO STANDARDS.
2. CONCRETE COMPRESSIVE STRENGTH 4,000 PSI MINIMUM.
3. STEEL REINFORCING DESIGN TO CONFORM TO THE REQUIREMENTS OF ASTM C890 SPECIFICATIONS FOR "STRUCTURAL DESIGN LOADING FOR WATER AND WASTEWATER STRUCTURES" AND SHALL UTILIZE GRADE 60 RE-BARS CONFORMING TO THE REQUIREMENTS OF ASTM A615 OR WWF CONFORMING TO THE REQUIREMENTS OF ASTM A185 OR BOTH. ADDITIONAL REINFORCING AT OPENINGS.
4. DESIGNED FOR H-20-44 LOADING.
5. STEPS REQUIRED ON CURB INLETS OVER 3'-6" IN DEPTH. STEPS SHALL BE STEEL REINFORCED COPOLYMER POLYPROPYLENE PLASTIC AND MEET THE REQUIREMENTS OF ASTM C478.
6. TOTAL HEIGHT PER JOB SPECIFICATIONS.
7. PIPE PENETRATION TO BE AS PER JOB REQUIREMENTS. PIPE TO BE INSTALLED BY CONTRACTOR AS PER NCDOT REQUIREMENTS FOR MORTAR JOINT CONNECTIONS.
8. CAST IN FRAME AND COVER PER GREENSBORO STANDARD DETAIL #411. SUPPLIED BY EITHER P.C.M. OR CUSTOMER.
9. JOINTS TO BE SEALED WITH BUTYL RUBBER JOINT SEALANT CONFORMING TO THE REQUIREMENTS OF ASTM C990, OR MORTAR AS PER NCDOT REQUIREMENTS, OR BOTH.
10. 8" TO 10" WEIR TYPICAL ON FRONT SIDE.

**2'-5" x 4'-10" CURB INLET  
GREENSBORO STANDARD #402**